	ORS FOR BIO - INCUBATOR @ IITMRP & IIT, MA	ADRAS	-	-	
	& INSTALLATION OF MODULAR WORKS				
SHA & PRADEE	PARCHITECTS		, ,		
NOTES					
NOTES		4- 1			-11
1	Detailed shop drawings, samples and colour schemes h		proved by	architects for	all components before
	2 Rate to include supply and instalation including all taxes.				
	Rate to include marking more than once and coordinating	g with other	contractors	s to ensure pr	oper entry of electrica
	4 Delivery period : 4 weeks				
S.No.	Item Description	QTY	Unit	Rate	TOTAL
PART 1	WORKSTATIONS				
1.0	Linear workstations				-
	Providing and fixing of Desk based modular work stations -Table top to be 18-19mm thick PLB with laminate finish on both sides and with PVC edge banding, table top to be supported on powder coated M.S legs as per propritery design approved by architects. Total partition height to be 1200mm and table size 1500X600 mm. Privacy panels with 25mm anodised / powder coated aluminium framework to have softboards tackable on both sides upto 1200mm with one data and one electrical raceway as per proprietary design. Rate to include pre-laminated lockable drawer 150mm high, pull out (metal or FRP as per approved sample) key board tray with sliding mouse tray and suspended swivel type CPU trolley, wire manager 65 dia and bag hook. all complete. The privacy screen to extend till 300mm above the FFL.	1.0	NO		
1.1	L shaped workstations				
а	Same as above but for straight workstations of size 1500x1200	6.0	NOS		
b	Same as above but for straight workstations of size 1500x1500	6.0	NOS		
1.2	Accessories				
а	Pedestals				
	Pre-laminated lockable pedestal with 3 drawers for all workstations	13.0	NOS		
	B Reception table	1.0	NOS		
	Providing and fixing Reception table consisting of the following components which include:				
System	Desking system with privacy panels and pole or cable masts				

Work surfaces	Size (1500x600mm) . Work surface formed out of 25mm thick particle boardcut to shape as shown in layout plan. Top						
	finised with approved laminate and PVC edge banded on all						
	sides. Wire managers (2 nos) to be provided.						
Modesty panel	Modesty panel with powder coated metal finish with or						
	without perforations as per approved sample.						
Base	Base shall be provided with MS powder coating finish with						
	cable masts, poles or vertebrae for cable management						
Wire	Powder coated cable masts/ poles or vertebrae for vertical						
Management	travel of cables. Cable beams below worktops for horizontal travel of cables.						
Storages	Return unit to have 2 pencil drawers and 2 shutters each with 1 intermideate shelves.						
0.0.4900							
Accessories	PVC keyboard tray and 1 no suspended, fixed metal powder						
	coated CPU holder.						
С	STORAGES						
	Providing and placing in position Pre-laminated storages units as per details given below						
Construction	Carcass for the storage to be made with 18mm prelaminated particle board.						
Shutter	Same as above						
Intermediate shelves	Same as above supported on suitable number of SS support pins and adjustable in height.						
Hardware	All storgaes to be lockable. Kich/ Godrej./ EBCO make						
	multipurpose locks and C type brushed SS handles and						
	tower bolts to be used. Magnet catches to be provided for all						
1	shutters. Storage unit 600 deep and 750 high 1200 mm long with		1				
·	100mm skirting box	9.0	NOS				
2	Storage unit 600 deep and 2100 high 4000 mm long with	1.0	NOS				
	100mm skirting box	1.0					
			GRA	ND TOTAL			
	TAX						