PROPOSED INTERIORS FOR BIO - INCUBATOR PHASE 2 - TENDER #4					
S.No.	Item Description	Qty	Unit	Rate	Total
A	Storage and display				
1	750mm high low ht laminated storage				
	750mm high, 600 deep and 1200 long Storage - Providing and fixing Low Ht. Storage made with 18 mm MDF, including shutters. The external surfaces of MDF to have 1 mm laminate finish and inside with enamel paint. Rate to include 4" high laminated skirting and all hardware, good quality SS handles, multipurpose lock etc. all complete.	9.0	NOS		
2	Overhead Storage				
	Over head storage - Waterproof plywood as it for pantry. Same as above but with laminated finish on the shutters also.	2.0	SQM		
3	Pantry counter and storage				
	Storage in pantry - 600mm depth, 820mm high with granite top - Providing and fixing in position storage made of waterproof ply with 20mm thk. polished granite top with edge as per profile in drawing. storage box construction. Unit to have shutter storage below. Rate to include making skirting, groves, all hardware etc. all complete. Shutters to have laminated finish with pattern as per drg. Elevation area considered for quantity measurement.	QRO	SQM		
4	DB shutters/ battery rack shutters.				
	P&F laminated shutters tp conceal Elec DB's at various locations made with 19mm thk waterproof plywood. Rate to include providing Aluminium frame all-round and at 450mm C/C vertically to avoid bend in shutter, concealed type hinges and dead lock and recessed handles and concealed tower bolts. Typical shutter width not to exceed 450 mm.	5.0	SQM		
	Total of Part A				
В	Furniture				
1	Reception table - Approx. sixe 1500x 600mm. Table to have curved front vertical panel duco painted with provision for lighting. 2 tier table with top ledge at 4' height, 1' 6" wide made of 12 toughned glass and to rest on 40 dia ss sections. Table to have duco painting, lamination; storage about 2' wide to the height of table, all complete. Table to sit on SS square legs.	1.0	NOS		
	Total of Part B				
	GRAND TOTAL				
	TAXES				