

PROPOSED INTERIORS FOR BIO - INCUBATOR @ IITMRP & IIT ,Madras.

PLUMBING RELATED WORKS

S.No	Item Description	Qty	Unit	Rate	Amount
A	Plumbing works				
a	GI Pipes class – C with pipe specials				
	<p>Supplying and fixing approved make GI Pipes – Class – C - heavy grade and pipe special with threaded / flanged joints cutting the pipes, laying to slopes where required fixing to perfect testing for joints and the materials, cutting grooves to conceal the pipes, making holes in all surfaces, restoring the damaged portions with required materials, etc. complete.</p> <p>Quoted rate shall include labour charges and (a) cost of specified material in the item description for the requirement, Cutting the pipes to required length, Fixing pipe with pipe specials as specified by the manufacturer with required fixing materials, Cutting groove on walls / floor to conceal the pipe work, Restoring damaged portion with required materials , Providing and removing necessary scaffolding, Two coats of bitumen painting, Conducting testing, Storing the materials, lead and lifting charges to all locations and at all floors with in the site, Providing MS angle supports for pipes laid in false ceiling using G.I.hangers fixed to R.C.C slab including providing and fixing necessary anchor fastners and clamps providing insulation (Vidoflex) and as directed by the engineer in-charge etc. complete</p>	70	RM		
b	SS - 304 with pipe specials				

	<p>Supplying and fixing approved make SS – 304 pipe special with welded / flanged joints cutting the pipes, laying to slopes where required fixing to perfect testing for joints and the materials, cutting grooves to conceal the pipes, making holes in all surfaces, restoring the damaged portions with required materials, etc. complete.</p> <p>Quoted rate shall include labour charges and (a) cost of specified material in the item description for the requirement, Cutting the pipes to required length, Fixing pipe with pipe specials as specified by the manufacturer with required fixing materials, Cutting groove on walls / floor to conceal the pipe work, Restoring damaged portion with required materials , Providing and removing necessary scaffolding, Conducting testing, Storing the materials, lead and lifting charges to all locations and at all floors with in the site, Providing MS angle supports for pipes laid in false ceiling using G.I.hangers fixed to R.C.C slab including providing and fixing necessary anchor fastners and clamps, providing insulation (Vidoflex) and as directed by the engineer in-charge etc. complete</p>	QRO			
TOTAL					
TAX					
GRAND TOTAL					