



INDIAN INSTITUTE OF TECHNOLOGY, MADRAS
CHENNAI - 600 036

Quotation Notice

Q. No. 03/2014-15/ELDB

Date: 11.08.2014

Sealed Quotations are invited from the HVAC contractors for the work of "Supply of 1.0 TR split ACs to network rooms and remote telephone exchange in various locations of IIT Madras. ". The filled in Quotation may be put in a cover super-scribed with name of the work, quotation number and date of receipt of quotation and addressed to Executive Engineer (Electrical), Engineering Unit, I.I.T., Madras, Chennai-600 036. The quotation may be sent to the Office of Executive Engineer (Electrical), EPABX Telephone Exchange 1st Floor, Near Administrative Building, IIT Madras on or before **22.08.2014**. The quotation sent by fax and e-mail will not be accepted.

Quotation No	Name of Work and Location	Approx. value of work in Rupees	EMD In Rs.	Last date for submission of Quotation
Q.No:03/2014-15/ Eldb	Supply of 1.0 TR split ACs to network rooms and remote telephone exchange in various locations of IIT Madras.	10.00 lakhs	20,000/-	22.08.2014

Signature of the contractor

Sd/-
Consultant (Elect)

Sd/-
Executive Engineer (E)

Name of Work: Supply of 1.0 TR split ACs to network rooms and remote telephone exchange in various locations of IIT Madras.

Sealed quotation are invited to Supply of 1.0 TR split type ACs to network rooms & remote telephone exchange to various locations from the reputed dealers/manufacturers as per the given below.

S.no	Description of Works	Qty	Unit	Rate	Amount
	PART-A- New items				
1	1.0 TR Split type units(both Indoor & outdoor) with hermetically sealed rotary type compressor, copper heat exchangers, EER not less than 3.40 & sound level not more than 47 db(A) for indoor and 54 db(A) for outdoor unit. The preferred make will be Hitachi/O General/Daikin. The rate shall inclusive of refrigerant Copper tubing with foam insulation clamping & copper chord wire upto 4.0 meters.				
	Supply	44	No.		
Rate in words Rupees					
	Installation	44	No.		
Rate in words Rupees					
2	Additional Refrigerant Copper tubing with foam insulation & GI clamping	22	Meter		
Rate in words Rupees					
3	20 mm dia PVC water line drain pipe(4 kg/sq.cm) with clamping on wall	120	Meter		
Rate in words Rupees					
4	Mounting angle of reputed make	44	Each		
Rate in words Rupees					

5	Electronics/Analog timer of reputed make to control 2 ACs in one location to enable automatic operation of 1 AC at a time at a span of 8 hours with necessary wirings as required.	22	Each		
Rate in words Rupees					
Total -Part A - Supply of new items					
Part- B -BUY back of old ACs					
6	Less buy back cost of following capacity/type of existing ACs after erecting the new ACs. The charges inclusive of dismantling the existing ACs, taken back by the contractor. The rate shall be quoted after accessing the value of ACs. The buyback value will be deducted from the total cost. The contractor should quote negative value for this item.				
a	1.5 TR window ACs(Make Voltas-year of purchase 2004)	7	Each		
Rate in words Rupees					
b	1.0/1.5/2.0 TR split ACs(Indoor & outdoor units with old copper tubes)- Make: LG/Samsung/Voltas-year of purchase 2004-2006)	23	Each		
Rate in words Rupees					
Total -Part B - Buyback items					
Total (Part A- Part B)					

Total in Words Rupees.....
.....only)

Terms & Conditions

1. The quotation should be submitted on or before **22/08/2014 at 3.00 pm** at the office of the Executive Engineer (Elec) in closed sealed cover either in person or by post so as to reach us at the above mentioned date & time. The quotation thro' e-mail will not be accepted.
2. The supply shall be 15 days from the date of purchase order. The rates quoted shall be inclusive of all taxes.
3. The supplier should submit the phamlet of the machine to be proposed for supply.
4. No advance payment and the payment shall be made on receipt of invoice after effecting the supply of machines. The payment of low side work will be given after commissioning of the machine.
5. The successful tenderer will have to arrange all the tools & ladder for the work and minor civil works such as closing of the holes for refrigerant pipes/drain pipes with cement plastering.

Sd/-
Executive Engineer (Elec)