

Corrigendum

Tender No: 24/2013-2014/Eldb

Date : 27.08.2013

Name of work : Electrification to proposed building for Main, PC and FTC for National Center for Combustion Research &Development (NCCRD) at IIT Madras.

Sl.No	Queries From Rotmax Engineering Enterprises Pvt Ltd	IITM Clarification
1	BOQ item No .15.1 to 18.3	The perforated cable tray and its accessories shall be GI only and the word MS may be read as GI
2	BOQ item No .25	The air insulated BBT may be considered.
3	BOQ item No .26	63 A Tap off units are for 250 amps BBT and other tap of units are in the rising main.
4	BOQ item No .30 to 33 &35	Company made sheet steel enclosure shall be used
5	BOQ item No .46	3 Core 2.5 Sq.mm copper flexible cable instead of 3x 2.5 sq.mm copper flexible cable
6	BOQ item No . 47	3 Core 4 Sq.mm copper flexible cable instead of 3x 4 sq.mm copper flexible cable
7	BOQ item No .48 to 51	Please read as multistranded instead of flexible
8	Modular switches /Sockets	As it is in the list of approved makes.
9	MCB/MCCB DBs	Consider only LEGRAND /HAGER make. However the sample to be approved by IIT Madras.

-Sd-
Executive Engineer (E)

-Sd-
Consultant (Elect)