INDIAN INSTITUTE OF TECHNOLOGY MADRAS Chennai 600 036

Telephone: [044] 2257 9763 E-mail: tender@imail.iitm.ac.in



Date:20.03.2023

The Manager (Project Purchase)

Open Tender Reference No: PH/ABHI/06/IOE23/CLEANROOM

GEM NAR ID: GEM/GARPTS/20032023/L1DQKVPH8VIO

Due Date/Time: 10.04.2023@ 3:00 PM

Dear Sir/Madam,

On behalf of the Indian Institute of Technology Madras, Tenders are invited in two bid system from Class-I local

suppliers and Class II local suppliers, for the supply of "Construction of class 10,000 and class 1000 Clean room" Conforming to the specifications given in Annexure -A.

Tender Documents may be downloaded from Central Public Procurement Portal <u>https://etenders.gov.in/eprocure/app</u>. Aspiring Bidders who have not enrolled / registered in e-procurement should enroll / register before participating through the website <u>https://etenders.gov.in/eprocure/app</u>. The portal enrolment is free of cost. Bidders are advised to go through instructions provided at **"Help for contractors"**. [Special Instructions to the Contractors/Bidders for the e-submission of the bids online through this eProcurement Portal"]

Bidders can access tender documents on the website (For searching in the NIC site, kindly go to Tender Search option and type 'IIT'. Thereafter, click on "GO" button to view all IIT Madras tenders). Select the appropriate tender and fill them with all relevant information and submit the completed tender document online on the website <u>https://etenders.gov.in/eprocure/app</u> as per the schedule attached.

1)	Pre-bid Meeting Details	:	NA
<u>2)</u>	ICSR Vendor Registration	:	<u>Vendor registration code</u> . Vendor registration with IC&SR (IITM) is mandatory for bidders to participate in tenders.
			** For Vendor Registration & Guidelines, Please follow the website : https://icandsr.iitm.ac.in/vendorportal; Helpdesk: <u>vendorhelpdesk@icsrpis.iitm.ac.in</u>

<u>No manual bids will be accepted.</u> All tender documents including Technical and Financial bids should be submitted in the E-procurement portal.

Last date for receipt of tender	:	10.04.2023 @ 3:00 PM
Date & time of opening of tender	:	11.04.2023 @ 3:00 PM

<u>3. Instructions to the Bidder:</u>

<u>A)</u>	Searching for tender documents	:	• There are various search options built in the CPP Portal, to facilitate bidders to search active tenders by several parameters. These parameters could include Tender ID, organization name, location, date, value, etc. There is also an option of advanced search for tenders, wherein the bidders may combine a number of search parameters such as organization name, form of contract, location, date, other keywords etc. to search for a tender published on the CPP Portal.
			• Once the bidders have selected the tenders they are interested in, they may download the required documents / tender schedules. These tenders can be moved to the respective "My Tender" folder. This would enable the CPP Portal to intimate the bidders through SMS / email in case there is any corrigendum issued to the tender document.
			• The bidder should make a note of the unique Tender ID assigned to each tender, in case they want to obtain any clarification / help from the Helpdesk.
<u>B)</u>	Assistance to bidders	:	 Any queries relating to the tender document and the terms and conditions contained therein should be addressed to the Tender Inviting Authority for a tender or the relevant contact person indicated in the tender. Any queries relating to the process of online bid submission or queries relating to CPP Portal in general may be directed to the 24x7 CPP Portal Helpdesk. The contact number for the helpdesk is [0120-4200462, 0120-4001002, 0120-4001005]
<u>C)</u>	Enrollment Process to Bidders	:	 REGISTRATION Bidders are required to enroll on the e-Procurement module of the Central Public Procurement Portal URL:https://etenders.gov.in/eprocure/app by clicking on "Online Bidder Enrollment". Enrollment on the CPP Portal is free of charge. As part of the enrolment process, the bidders will be required to choose a unique username and assign a password for their accounts. Bidders are advised to register their valid email address and mobile numbers as part of the registration process. These would be used for any communication from the CPP Portal. Upon enrolment, the bidders will be required to register their valid Digital Signature Certificate (Class II or Class III Certificates with signing key usage) issued by any Certifying Authority recognized by CCA India (e.g. Sify / TCS / nCode / eMudhra etc.) Only one valid DSC should be registered by a bidder. Please note that the bidders are responsible to ensure that they do not lend their DSCs to others which may lead to misuse. Bidder then may log in to the site through the secured log-in by entering their user ID / password and the password of the DSC / eToken. Possession of a Valid Class II/III Digital Signature Certificate

			 (DSC) in the form of smart card/e-token in the company's name is a prerequisite for registration and participating in the bid submission activities through https://etenders.gov.in/eprocure/app Digital Signature Certificates can be obtained from the authorized certifying agencies, details of which are available in the web site https://etenders.gov.in/eprocure/app under the "Information about DSC".
<u>D)</u>	Preparation of bids	•	Bidder should take into account any corrigendum published on the tender document before submitting their bids.
		•	Please go through the tender advertisement and the tender document carefully to understand the documents required to be submitted as part of the bid. Please note the number of covers in which the bid documents have to be submitted, the number of documents including the names and content of each of the document that need to be submitted. Any deviations from these may lead to rejection of the bid.
		•	Bidder, in advance, should prepare the bid documents to be submitted as indicated in the tender document / schedule and generally shall be in PDF / XLS formats as the case may be. Bid documents may be scanned with 100 dpi with black and white option. To avoid the time and effort required in uploading the same set of standard documents which are required to be submitted as a part of every bid, a provision of uploading such standard documents (e.g. PAN card copy, GSTIN Details, annual reports, auditor certificates etc.) has been provided to the bidders. Bidders can use "My Documents " area available to them to upload such documents. These documents may be directly submitted from the "My Documents " area while submitting a bid, and need not be uploaded again and again. This will lead to a reduction in the time required for bid submission process.
<u>E)</u>	Submission of bids	•	Bidder should log into the site well in advance for bid submission so that he/she can upload the bid in time i.e. on or before the bid submission date and time. Bidder will be responsible for any delay due to other issues.
		•	The bidder has to digitally sign and upload the required bid documents one by one as indicated in the tender document.
		•	Bidder has to select the bid security declaration. Otherwise, the tender will be summarily rejected.
		•	A standard BOQ format has been provided with the tender document to be filled by all the bidders. Bidders are requested to note that they should necessarily submit their financial bids in the format provided and no other format is acceptable. Bidders are required to download the BOQ file, open it and complete the detail with their respective financial quotes and other details (such as name of the bidder). If the BOQ file is found to be modified by the bidder, the bid will be rejected.
		•	The server time (which is displayed on the bidders' dashboard) will be considered as the standard time for referencing the deadlines for submission of the bids by the bidders, opening of bids etc. The

		bidders should follow this time during bid submission.
		• The Tender Inviting Authority (TIA) will not be held responsible for any sort of delay or the difficulties faced during the submission of bids online by the bidders due to local issues.
		• The uploaded tender documents become readable only after the tender opening by the authorized bid openers.
		• Upon the successful and timely submission of bids, the portal will give a successful bid submission message & a bid summary will be displayed with the bid no. and the date & time of submission of the bid with all other relevant details.
		 Kindly add scanned PDF of all relevant documents in a single PDF file of compliance sheet. More information useful for submitting online bids on the CPP Portal may be obtained at: <u>https://etenders.gov.in/eprocure/app</u>. All tender documents including pre-qualification bid, Technical Bid &Financial Bid should be submitted separately in online CPP portal as per the specified format only. Right is reserved to ignore any tender which fails to comply with the above instructions. No manual bid submission will be entertained.
<u>F)</u>	Marking on Technical Bid	• The bidder eligibility criteria, technical specification and supply of item for this tender is given in Annexure A.
		• The Bidders shall go through the specification and submit the technical bid.
		• The Technical bid should be submitted in the proforma as per Annexure-B in pdf format only through online (e-tender). No manual submission of bid will be entertained.
		• The technical bid should have a page-wise heading as "Technical Bid" and page no. in all pages with seal and signature of authorized signatory. The total no. of pages should be mentioned at the last page of the documents.
		• The technical bid should consist of bidder eligibility criteria details and all technical details along with catalogue/ pamphlet which will give a detailed description of product with technical data sheet so that technical compliance can be verified.
<u>G</u>)	Marking on Price Bid	• Financial bid (BoQ) should be submitted in the prescribed proforma format as per Annexure-C in xls format through e-tender only. No manual or other form of submission of Financial Bid will not be entertained

4) **Preparation of Tender**: The bidders should submit the bids in two bid system as detailed below.

Bid I _ Technical Bid

The technical bid should consist of bidder eligibility criteria and technical specification compliance sheet as per Annexure-B.

Bid II _Price Bid

The price bid should be submitted in excel format (BoQ) as per the proforma (Annexure C) uploaded in the e-Tender web site. The Quoted price should be for supply and installation of the item and inclusive of all cost and statutory levies at IIT Madras.

5)	Price:
	a) The price should be quoted only in INR net per unit (after breakup) and must include all packing, transit insurance and delivery charges to the entry of Department of Physics.
	b) The rate quoted shall be all inclusive of all taxes and no extra payment will be made other than statutory revisions as per the terms and conditions stipulated in this contract document.
	c) The percentage of tax & duties should be clearly indicated separately. IIT Madras is eligible for custom duty (5.5%). Relevant certificates will be issued wherever necessary.
	d) The offer/bids should be submitted through online only in two bid system i.e. Technical Bid and Financial Bid separately.
6)	Tenderer shall submit along with this tender:
	(i) Proof of having ISO or other equivalent certification given by appropriate authorities.
	(ii) Name and full address of the Banker and their swift code and PAN No. and GSTIN number.
	(iii) GST registration proof showing registration number, area of registration etc.
	(iv) All of your future correspondences including Invoices should bear the GST No. and Area Code.
7)	Terms of Delivery:
	Supplier will be fully responsible for the safe carriage, Installation/Commissioning of goods up to the Department of Physics , IIT Madras or named place as per PO, Insurance coverage will be in the scope of the supplier.
	The tenderer should indicate clearly the time required for delivery of the item (subject to the approval of the Executive Committee-IIT-Madras). In case there is any deviation in the delivery schedule, liquidated damages clause will be enforced or penalty for the delayed supply period will be levied.
	In the event of delay or non-supply of materials/execution of Contract beyond the date of delivery/completion of job. The penalty will be levied @1% per week of delay subject to a max of 10% of the value of purchase order and if the delay is more than accepted time frame by IIT M, the PO would be partially or fully cancelled and liquidated damages will be enforced accordingly.
8)	Period for which the offer will remain open:
	The Tender shall remain open for acceptance/validity till: 120 days from the date of opening of the tender. However, the day up to which the offer is to remain open being declared closed holiday for the Indian Institute of Technology Madras, the offer shall remain open for acceptance till the next working day.
9)	EMD:
	The EMD of Rs.70,000 to be transferred to the account details mentioned in Annexure D and proof should be enclosed in the Technical Bid. Any offer not accompanied with the EMD shall be rejected summarily as non-responsive. The EMD of the unsuccessful bidders shall be returned within 30 days of the end of the bid validity period. The same shall be forfeited, if the tenderers withdraw their offer after the opening during the bid validity period. The Institute shall not be liable for payment of any interest on EMD. EMD is exempted for Micro and Small Enterprises (MSE) as defined in MSE Procurement Policy issued by Department of Micro, Small and Medium Enterprises (MSME) and Startups as recognized by Department of Industrial Policy & Promotion (DIPP). (MSE/MSME/DIPP PROOF should be enclosed in the cover containing technical bid)

10)	Performance Security: -
	The successful bidder should submit Performance Security for an amount of 3% of the value of the contract/supply. The Performance Security may be furnished in the form of an Account Payee DD, FD Receipt in the name of "The Registrar, IIT Madras" from any scheduled commercial bank or Bank Guarantee from any scheduled commercial bank in India. The performance security should be furnished within 14 days from the date of the purchase order.
	Performance Security in the form of Bank Guarantee: - In case the successful bidder wishes to submit Performance Security in the form of Bank Guarantee, the Bank Guarantee should be routed directly to IIT Madras from the Bank.
	The Bank Guarantee should remain valid for a period of sixty days beyond the date of completion of all contractual obligations of the supplier including the warranty obligations.
11)	For the same tender, either the OEM or the authorized dealer/service provider can only quote. But both of them cannot quote separately for the same tender.
12)	The offers/bids should be sent only for a item/Equipments of latest version that is available in the market and supplied to a number of customers. A list of customers in India with details must accompany the quotations. Quotations for a prototype machine will not be accepted
13)	Original catalogue (not any photocopy) of the quoted model duly signed by the principals must accompany the quotation in the Technical bid.
14)	Compliance or Confirmation report with reference to the specifications and other terms & conditions should also be obtained from the principal/OEM.
15)	Risk Purchase Clause
	In the event of failure of supply of the item/equipment within the stipulated delivery schedule, the purchaser has all the right to purchase the item/equipment from other sources on the total risk of the supplier under risk purchase clause.
16)	Payment:
	(i) No Advance payment will be made. However, 90% Payment against Delivery and 10% after installation are agreed to wherever the installation is involved.
	(ii) Advance Payment: No advance payment is generally admissible. In case a specific percentage of advance payment is required, the Vendor has to submit a Bank Guarantee from a scheduled commercial bank in India equivalent to the amount of advance payment.
17)	On-site Installation:
	The equipment/item or Machinery has to be installed or commissioned by the successful bidder within the number of days (as prescribed by PI) from the date of receipt of the item at the site of IIT Madras.
18)	Warranty/Guarantee:
	The offer should clearly specify the warranty or guarantee period for the machinery/equipment. Any extended warranty offered for the same has to be mentioned separately (For more details please refer our Technical Specifications).
	** Note: PO which involves installation, warranty/guarantee shall be applicable from date of installation.
19)	Acceptance and Rejection:
	Failure to comply with any of the instructions stated in this document or offering unsatisfactory explanations for non-compliance will likely to lead to rejection of offers.
	I.I.T. Madras has the right to accept the whole or any part of the Tender or portion of the quantity offered or reject it in full without assigning any reason.

 In case of breach of Terms & Conditions, Bidder may be suspended from being eligible for bidding in any contract with the IIT Madras up to 2 Years [as per Rule 151(iii) of GFR] from the date of Tender. Disputes and Jurisdiction: Settlement of Disputes: Any dispute, controversy or claim arising out of or in connection with this PO including any question regarding its existence, validity, breach or termination, shall in the first instance be attempted to be resolved amicably by both the Parties. If attempts for such amicable resolution fails or no decision is reached within 30 days whichever is earlier, then such disputes shall be settled by arbitration in accordance with the Arbitration and Conciliation Act, 1996. Unless the Parties agree on a sole arbitrator, within 30 days from the receipt of a written request by one Party from the other Party to so agree, the arbitral panel shall comprise of three arbitrators. In that event, the supplier will nominate one arbitrator and the Project Coordinator of IITM shall nominate on arbitrator. The Dean IC&SR will nominate the Presiding Arbitrator of the arbitral tribunal. The arbitration proceeding shall be carried out in English language. The cost of arbitration and fees of the arbitrator(s) shall be shared equally by the Parties. The seat of arbitration shall be at IC&SR IIT Madras, Chennai. a. The Applicable Law: The Purchase Order shall be construed, interpreted and governed by the Laws of India. Court at Chennai shall have exclusive jurisdiction subject to the arbitration clause. b. Any legal disputes arising out of any breach of contact pertaining to this tender shall be settled in
 Settlement of Disputes: Any dispute, controversy or claim arising out of or in connection with this PO including any question regarding its existence, validity, breach or termination, shall in the first instance be attempted to be resolved amicably by both the Parties. If attempts for such amicable resolution fails or no decision is reached within 30 days whichever is earlier, then such disputes shall be settled by arbitration in accordance with the Arbitration and Conciliation Act, 1996. Unless the Parties agree on a sole arbitrator, within 30 days from the receipt of a written request by one Party from the other Party to so agree, the arbitral panel shall comprise of three arbitrators. In that event, the supplier will nominate one arbitrator and the Project Coordinator of IITM shall nominate on arbitrator. The Dean IC&SR will nominate the Presiding Arbitrator of the arbitral tribunal. The arbitration proceeding shall be carried out in English language. The cost of arbitration and fees of the arbitrator(s) shall be shared equally by the Parties. The seat of arbitration shall be at IC&SR IIT Madras, Chennai. a. The Applicable Law: The Purchase Order shall be construed, interpreted and governed by the Laws of India. Court at Chennai shall have exclusive jurisdiction subject to the arbitration clause.
 including any question regarding its existence, validity, breach or termination, shall in the first instance be attempted to be resolved amicably by both the Parties. If attempts for such amicable resolution fails or no decision is reached within 30 days whichever is earlier, then such disputes shall be settled by arbitration in accordance with the Arbitration and Conciliation Act, 1996. Unless the Parties agree on a sole arbitrator, within 30 days from the receipt of a written request by one Party from the other Party to so agree, the arbitral panel shall comprise of three arbitrators. In that event, the supplier will nominate one arbitrator and the Project Coordinator of IITM shall nominate on arbitrator. The Dean IC&SR will nominate the Presiding Arbitrator of the arbitral tribunal. The arbitration proceeding shall be carried out in English language. The cost of arbitration and fees of the arbitrator(s) shall be shared equally by the Parties. The seat of arbitration shall be at IC&SR IIT Madras, Chennai. a. The Applicable Law: The Purchase Order shall be construed, interpreted and governed by the Laws of India. Court at Chennai shall have exclusive jurisdiction subject to the arbitration clause.
the court of competent jurisdiction located within the city of Chennai in Tamil Nadu.
Force Majeure: The Supplier shall not be liable for forfeiture of its performance security, liquidated damages or termination for default, if and to the extent that, it's delay in performance or other failure to perform its obligations under the Contract is the result of an event of Force Majeure.
For purposes of this Clause, "Force Majeure" means an event beyond the control of the Supplier and not involving the Supplier's fault or negligence and not foreseeable. Such events may include, but are not limited to, acts of the Purchaser either in its sovereign or contractual capacity, wars or revolutions, fires, floods, epidemics, quarantine restrictions and freight embargoes.
If a Force Majeure situation arises, the Supplier shall promptly notify the Purchaser in writing of such conditions and the cause thereof. Unless otherwise directed by the Purchaser in writing, the Supplier shall continue to perform its obligations under the Contract as far as is reasonably practical, and shall seek all reasonable alternative means for performance not prevented by the Force Majeure event.
Eligibility Criteria:
As per the Government of India Order, only "Class - I Local Suppliers" and "Class - II Local Suppliers" <u>can participate in this tender.</u>
Bidder should confirm their acceptance that they comply with the provisions with report to "Guidelines for eligibility of a bidder from a country which shares a land border with India as detailed at Annexure-F. The bidder should submit Certificate for "Bidder from/ Not from Country sharing Land border with India & Registration of Bidder with Competent Authority" as per Order of DoE F.No.6/18/2019-PPD dated 23.07.2020 as mentioned.
Preference to "class I Local Suppliers" : preference will be given to " class 1 local suppliers " (subject to class -I local supplier's quoted price falling within the margin of purchase preference) as per public procurement (preference to make in India) order 2017 .O.M No P- 45021/2/2017 – pp(BE - 11) dt 04/06/2020 subject to the conditions that the "class 1 Local Supplier" should agree to supply goods / provide service at L1 rate and furnish a certificate with the technical bid document that the
P to p1

 Chartered Accountant in case value of contract exceeds Rs 10 crore). 'Class - I local supplier' means a supplier or service provider whose goods, services or works offered for procurement consists of local content equal to or more than 50% as defined under the above said order. Declaration to be provided as per Annexure-D per item/service/work. 'Class - II local supplier' means a supplier or service provider whose goods, services or works offered for procurement consists of local content equal to 20% but less than 50% as defined under the above said order. Declaration to be provided as per Annexure-D per item/service/work. 'Margin of purchase preference': - The margin of purchase preference bills be 20%. The Definition of the margin of purchase preference is defined in the Govt. of India Order No: P-45021/12/2017-PP (BE-II) Dt.4th June, 2020) Order 2017. As per the Government of India Order - "Margin of Purchase Preference" means the maximum extent to which the price quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase preference. **Note: Local content percentage to be calculated in accordance with the definition provided as clause 2 of revised public procurement preference to Make in India Policy vide GoI Order no. P-45021/12/2017-PP (BE-II) atted 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/22017-PP (BE II) Dt.16th September 2020 & P-45021/12/2019-BE-II-Par(1) (E-50310) Dt.4th March 2021 Evaluation of Bids Bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Stage II Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be		
 offered for procurement consists of local content equal to or more than 50% as defined under the above said order. Declaration to be provided as per Annexure-D per item/service/work. 'Class - II local supplier' means a supplier or service provider whose goods, services or works offered for procurement consists of local content equal to 20% but less than 50% as defined under the above said order. Declaration to be provided as per Annexure-D per item/service/work. 'Margin of purchase preference': - The margin of purchase preference shall be 20%. The Definition of the margin of purchase preference is defined in the Govt. of India Order No: P- 45021/12/2017-PP (BE-II) Dt.4th June, 2020) Order 2017. As per the Government of India Order - "Margin of Purchase Preference" means the maximum extent to which the price quoted by a "Class-1 local supplier" may be above the L1 for the purpose of purchase preference. **Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide GoI Order no. P- 45021/2/2017-PP (BE-II) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019.and 04.06.2020) MOCI order No. 45021/2/217-PP (BE II) Dt.16th September 2020 & P- 45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 Evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room" unit will alone be taken up for arrival of Lowset Bid (L1) value. Selection of successful bidder and Award of Order The render will be d		Chartered Accountant in case value of contract exceeds Rs 10 crore).
 Class - II local supplier' means a supplier or service provider whose goods, services or works offered for procurement consists of local content equal to 20% but less than 50% as defined under the above said order. Declaration to be provided as per Annexure-D per item/service/work. Margin of purchase preference': - The margin of purchase preference shall be 20%. The Definition of the margin of purchase preference is defined in the Govt. of India Order No: P-45021/12/2017-PP (BE-II) Dt.4th June, 2020) Order 2017. As per the Government of India Order – "Margin of Purchase Preference" means the maximum extent to which the price quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase preference. **Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide Gol Order no. P-45021/12/2017-PP (BE-LI) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-45021/10/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 Evaluation of Bids Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room" unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technical valuation finding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the same. If any deviation found in the sam		offered for procurement consists of local content equal to or more than 50% as defined under the
 offered for procurement consists of local content equal to 20% but less than 50% as defined under the above said order. Declaration to be provided as per Annexure-D per item/service/work. 'Margin of purchase preference': - The margin of purchase preference shall be 20%. The Definition of the margin of purchase preference is defined in the Govt. of India Order No: P-45021/12/2017-PP (BE-II) Dt.4th June, 2020) Order 2017. As per the Government of India Order - "Margin of Purchase Preference" means the maximum extent to which the price quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase preference. **Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide Gol Order no. P-45021/12/2017-PP (BE-II-) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 Evaluation of Bids Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II Perheid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technical yqualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the same. If any deviation found in the same at any stage and da		
 the above said order. Declaration to be provided as per Annexure-D per item/service/work. 'Margin of purchase preference': - The margin of purchase preference shall be 20%. The Definition of the margin of purchase preference is defined in the Govt. of India Order No: P 45021/12/2017-PP (BE-II) Dt.4th June, 2020) Order 2017. As per the Government of India Order - "Margin of Purchase Preference" means the maximum extent to which the price quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase preference. **Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide Gol Order no. P. 45021/22017-PP (B.EII) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P 45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation		
 Margin of purchase preference': - The margin of purchase preference shall be 20%. The Definition of the margin of purchase preference is defined in the Govt. of India Order No: P-45021/12/2017-PP (BE-II) Dt.4th June, 2020) Order 2017. As per the Government of India Order - "Margin of Purchase Preference" means the maximum extent to which the price quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase preference. **Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide GoI Order no. P-45021//2/2017-PP (BE-II) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room" unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejectio		offered for procurement consists of local content equal to 20% but less than 50% as defined under
Definition of the margin of purchase preference is defined in the Govt. of India Order No: P-45021/12/2017-PP (BE-II) Dt.4th June, 2020) Order 2017. As per the Government of India Order - "Margin of Purchase Preference" means the maximum extent to which the price quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase preference. ***Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide GoI Order no. P-45021/2/2017-PP (B.EII) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 20.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 25) Evaluation of Bids Bid evaluation Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II : Price Bid Evaluation The price Bid Evaluation The price Bid Evaluation The price Bid Evaluation Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. 26) Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. 27) All information including selection and rejection of technical or financial bids of the prospective bidders will be eithietly to question th		
 45021/12/2017-PP (BE-II) Dt.4th June, 2020) Order 2017. As per the Government of India Order - "Margin of Purchase Preference" means the maximum extent to which the price quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase preference. **Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide GoI Order no. P-45021/2/2017-PP (BE-II) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Stage II: Price Bid Evaluation and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be instead as a corrigendun/addendum in the e-tenders portal. Due to Covid-19 pa		➤ 'Margin of purchase preference': - The margin of purchase preference shall be 20%. The
 Order - "Margin of Purchase Preference" means the maximum extent to which the price quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase preference. **Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide Gol Order no. P. 45021/2/2017-PP (B.EII) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P- 45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of Successful bidder and Award of Order The order will be directly awarded to the technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The therderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be instead as a corrigendun/addendum in the e-tenders portal. Due to Covid-19 pandemic th		
quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase preference.**Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide Gol Order no. P- 45021/2/2017-PP (B.EII) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 		45021/12/2017-PP (BE-II) Dt.4th June, 2020) Order 2017. As per the Government of India
 preference. **Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide GoI Order no. P-45021/2/2017-PP (B.EII) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the terminated and actions will be initiated as per the terms and conditions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract. <li< th=""><th></th><th>Order – "Margin of Purchase Preference" means the maximum extent to which the price</th></li<>		Order – "Margin of Purchase Preference" means the maximum extent to which the price
 **Note: Local content percentage to be calculated in accordance with the definition provided at clause 2 of revised public procurement preference to Make in India Policy vide GoI Order no. P-45021/2/2017-PP (B.EII) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019 and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation		quoted by a "Class-I local supplier" may be above the L1 for the purpose of purchase
 clause 2 of revised public procurement preference to Make in India Policy vide GoI Order no. P-45021/2/2017-PP (B.EII) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 25) Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room" unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as p		preference.
 45021/2/2017-PP (B.EII) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 25) Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation		**Note: Local content percentage to be calculated in accordance with the definition provided at
 29.05.2019and 04.06.2020) MOCI order No. 45021//2017-PP (BE II) Dt.16th September 2020 & P-45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 25) Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation		clause 2 of revised public procurement preference to Make in India Policy vide GoI Order no. P-
 45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021 25) Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. 260 Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. 271 All information including selection and rejection of functial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. 28) The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. 29) Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 		45021/2/2017-PP (B.EII) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018,
 25) Evaluation of Bids Bid evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room" unit will alone be taken up for arrival of Lowest Bid (L1) value. 26) Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. 27) All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. 28) The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. 29) Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 		29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P-
 Bid evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price Bid Evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 		45021/102/2019-BE-II-Part(1) (E-50310) Dt.4th March 2021
 Bid evaluation will take place in two stages. Stage I Technical Bid evaluation All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room" unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 	25)	Evaluation of Bids
 All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 	2 3)	Bid evaluation will take place in two stages.
 (Annexure A) will only be considered for opening of price bid. Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 		Stage I Technical Bid evaluation
 Stage II: Price Bid Evaluation The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the doubts raised by the bidders will not be en		All bidders who have fully complied with bidder eligibility criteria I, II and technical evaluation
 The price bid evaluation will be based on price quoted by the bidder. The rate quoted for "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 		(Annexure A) will only be considered for opening of price bid.
 "Construction of class 10,000 and class 1000 Clean room " unit will alone be taken up for arrival of Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 		Stage II: Price Bid Evaluation
 Lowest Bid (L1) value. Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 		The price bid evaluation will be based on price quoted by the bidder. The rate quoted for
 Selection of successful bidder and Award of Order The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 		
 The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 		
 The order will be directly awarded to the technically qualified bidder as per the condition in para 3A of DIPP, MoCI Order No. 45021/2/2017-PP (BE II) dated 16th September 2020. 27) All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. 28) The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. 29) Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will not be entertained to participate in opening of Bids. Since the 	26)	
 27) All information including selection and rejection of technical or financial bids of the prospective bidders will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. 28) The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. 29) Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. 30) Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the 	,	
 will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the 		
 will be communicated through e-Tender portal. In terms of Rule 173(iv) of General Financial Rule 2017, the bidder shall be at liberty to question the bidding conditions, bidding process and/or rejection of bids. The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the 	27)	
 28) The tenderer shall certify that the tender document submitted by him / her are of the same replica of the tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. 29) Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. 30) Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the 		
 tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the 		
 tender document as published by IIT Madras and no corrections, additions and alterations made to the same. If any deviation found in the same at any stage and date, the bid / contract will be rejected / terminated and actions will be initiated as per the terms and conditions of the contract. 29) Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. 30) Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the 	28)	
 terminated and actions will be initiated as per the terms and conditions of the contract. 29) Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. 30) Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the 	,	
 29) Due to Covid-19 pandemic pre-bid meeting will be conducted through online. Clarification to the queries and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. 30) Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the 		
 and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the 		
and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal. 30) Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the	29)	
		and doubts raised by the bidders will be issued as a corrigendum/addendum in the e-tenders portal.
tender is e-tender, the opening of the bids may be checked using the respective logins of the bidders.	30)	Due to Covid-19 pandemic the bidders will not be entertained to participate in opening of Bids. Since the
	50)	tender is e-tender, the opening of the bids may be checked using the respective logins of the bidders.

ACKNOWLEDGEMENT

It is hereby acknowledged that I/We have gone through all the points listed under "Specification, Guidelines, Terms and Conditions" of tender document. I/We totally understand the terms and conditions and agree to abide by the same.

SIGNATURE OF TENDERER ALONG WITH SEAL OF THE COMPANY WITH DATE

Bidder Eligibility Criteria and Technical Specification for "Construction of class 10,000 and class 1000 Clean room " Tender No. PH/ABHI/06/IOE23/CLEANROOM

Bidder Eligibility Criteria – I (Public Procurement – Preference to Make in India)

Only 'Class-I local suppliers' and 'Class-II local suppliers', as defined under DIPP, MoCI Order No. P-45021/2/2017-PP (BE-II) dated 16th September 2020 and other subsequent orders issued therein.

Bidder Eligibility Criteria – II

The bidder/OEM should have executed at least 3 similar works to IITs, NITs, IISERs, CSIR Labs or other Govt. organizations in the last 5 years, PO copies or installation certificates along with contact details of end user need to be submitted as the proof of supply. IIT Madras reserves its right to verify the claims submitted by the bidder and the feedback from the previous customers will be part of technical evaluation

II. Technical Specification For "Construction of class 10,000 and class 1000 Clean room "

Description: Through this tender, we invite the vendors to bid for constructing a class 10,000 and class 1000 Construction of class 10,000 and class 1000 Clean room (CR) in HSB 262 of the Physics department. Vendors should have constructed similar (class 10,000 and 1000) Construction of class 10,000 and class 1000 Clean room s in institutions such as IITs, IISc, and Govt. laboratories. Documentary proof in support of this should be provided with the institution Name, contact person Name, email Id, and Phone no.

Site information	
Floor	First floor
Area of class 10,000	329 Sq.Ft
Area of class 1000	144 Sq.Ft
Expected number of persons to work in CR	5
Temperature to be maintained	23 -24°C
Rel. Humidity	50

S.NO	SPECIFICATIONS
1	Air Conditioner unit should be with at least 10TR (5TR X 2 - Inverter) or higher capacity Air
1	Cooled condensing Unit with scroll compressor.
	Air Handling Unit should be double skin, 25mm PUF panels made of pre-coated sheets with
	aluminum sectional frames. It should have thermal break profile, 6-Row copper cooling coil of
2	capacity 10TR, pre-filters, bypass damper, fresh air arrangement etc. to achieve Class 1000/10000
	cleanliness. It should have a motor blower of capacity 5300cfm or higher.
	Refrigerant piping: Hard-drawn Copper pipes with accessories, fittings, supports, tubular nitrile
3	foam insulation complete with leak free brazed joints (up to 8 meters per circuit), N ₂ pressure tested,
	vacuum held & R407c/R410a refrigerant charged, including Drier, HS Valve & Expansion Valve.
	Terminal HEPA filters: to filter 0.3micron and larger particles at >99.97% efficiency installed in
4	specially designed insulated Plenum GI powder coated, installed in false ceiling in such a way that
т	the first air coming into the room is better than Class 100, with all provisions for HEPA filter
	Integrity test at Site.
5	Prefilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable
5	media with aluminum support mesh; to match AHU capacity
6	Ducting Factory fabricated rectangular duct, GI, 24G

20 21 22 23 24	 Epoxy flooring: Self leveling, seamless floor with suitable surface preparation, 3mm total thickness. Sockets: 15/5A in the Wall Panels / Partitions. Scope includes all wiring for lighting, sockets & switches complete within the Construction of class 10,000 and class 1000 Clean room area, including cutouts & conduits in Wall Panels. Smoke Detection and Alarm System: Conventional sensors (8Nos), Conventional control panel, Manual Call Point, Response Indicator, Audio-visual alarm, wiring/cabling Biometric Door Access Control System: with software, EM lock, exit push button, Switched -mode
21 22 23	Sockets: 15/5A in the Wall Panels / Partitions. Scope includes all wiring for lighting, sockets & switches complete within the Construction of class 10,000 and class 1000 Clean room area, including cutouts & conduits in Wall Panels. Smoke Detection and Alarm System: Conventional sensors (8Nos), Conventional control panel, Manual Call Point, Response Indicator, Audio-visual alarm, wiring/cabling
21 22	Sockets: 15/5A in the Wall Panels / Partitions. Scope includes all wiring for lighting, sockets & switches complete within the Construction of class 10,000 and class 1000 Clean room area, including cutouts & conduits in Wall Panels. Smoke Detection and Alarm System: Conventional sensors (8Nos), Conventional control panel,
21	Sockets: 15/5A in the Wall Panels / Partitions. Scope includes all wiring for lighting, sockets & switches complete within the Construction of class
20	
17	lamps of suitable wattage.
19	mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED
18	View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush
17	Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included.
	2.1m
16	with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X
	Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated
15	Corner Coving: Die cast aluminum coving for corners.
14	Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor.
	exposed EPS material
10	Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the
13	Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for
	Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling
	material and provision for concealed wiring, Return Air Risers.
12	panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS
12	It should have modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the
11	including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring.
11	Scope includes the electrical Work from Control Panel to the AHU & Condensing Units
10	Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No).
9	Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup.
	Fire Damper withfusible link and limit switch to cutoff power to AHU in case of fire.
8	Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock.
	exposed to sunlight with 0.4mm aluminum sheet.
1	and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly
7	Insulation: ducts insulated with cross-linked polyethylene of 13mm thick. All ducts should be sealed

TECHNICAL BID PROFORMA Tender No. PH/ABHI/06/IOE23/CLEANROOM Item Name: "Construction of class 10,000 and class 1000 Clean room "

Bidder Eligibility Criteria:

1.0	Bidder Eligibility Criteria-I (Public Procurement – Preference to Make in India)	Class I / Class II	Local Content value	Reference, Page No.
Ι	Only 'Class-I local suppliers' and 'Class-II local suppliers', as defined under DIPP, MoCI Order No. P-45021/2/2017-PP (BE II) dated 16 th September 2020 and other subsequent orders issued therein.			
2.0	Bidder Eligibility Criteria-II			
1	The bidder/OEM should have executed at least 3 similar works to IITs, NITs, IISERs, CSIR Labs or other Govt. organizations in the last 5 years, PO copies or installation certificates along with contact details of end user need to be submitted as the proof of supply. IIT Madras reserves its right to verify the claims submitted by the bidder and the feedback from the previous customers will be part of technical evaluation			

3.0 Technical Compliance:

Description: Through this tender, we invite the vendors to bid for constructing a class 10,000 and class 1000 Construction of class 10,000 and class 1000 Clean room (CR) in HSB 262 of the Physics department. Vendors should have constructed similar (class 10,000 and 1000) Construction of class 10,000 and class 1000 Clean room s in institutions such as IITs, IISc, and Govt. laboratories. Documentary proof in support of this should be provided with the institution Name, contact person Name, email Id, and Phone no.

Site information	
Floor	First floor
Area of class 10,000	329 Sq.Ft
Area of class 1000	144 Sq.Ft
Expected number of persons to work in CR	5
Temperature to be maintained	23 -24°C
Rel. Humidity	50

S.NO	SPECIFICATIONS	COMPLIED/NOT COMPLIED	REFERENCE PG.NO
1	Air Conditioner unit should be with at least 10TR (5TR X 2 - Inverter) or higher capacity Air Cooled condensing Unit with scroll compressor.		
2	Air Handling Unit should be double skin, 25mm PUF panels made of pre-coated sheets with aluminum sectional frames. It should have thermal break profile, 6-Row copper cooling coil of		

capacity 10TR, pre-filters, bypass damper, fresh air arrangement ect, o achieve Class 1000/10000 cleantiness. It should have a motor blower of capacity 5300cfm or higher. Refrigerant piping: Harl-drawn Copper pipes with accessories, fittings, supports, tabular mittle foam insulation complete with leak free brazed joints (up to 8 meters per circuit), Ns pressure tested, vacuum held & AdV07R410 net frigerant charged, including Drier, HS Valve & Expansion Valve. Terminal HEPA filters: to filter 0 simicron and larger particles at >99.97% efficiency installed in specially designed insulated Plenum GI powder coated, installed in filter stat Site. shuth and they Afficiency installed in filter stat Site. shuth and provisions for HEPA filter Integrity test at Site. shuth and provisions for HEPA filter Integrity test at Site. for more the state of the state of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity. for Instance duction unable with diverse – remenul with bandle with gradation markings and lock. Fire Damper withfusible link and first site on bight with 0.4mm aluminum sheet. 8 Volume control (GT + HEO) duct Dampers – manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch in oculor forwer in AHU in case of fire. 9 Return Air Risers embedded with mwall panels with extruded aluminum. Grills for lower paneyres – manual with latent fire. 10 Room Pressure Magnehelic Gauge with fisture (1No) & Tempers – manual with latent fire.			
motor blower of capacity 5300cfm or higher. Refrigerant piping: Hard-drawn Copper pipes with accessories, fittings, supports, tubular mittle foam insulation complete with leak free brazed joints (up to 8 meters per circuit), Ns pressure tested, vacum held & Red7o/R410 ner Origineran charged, including Drier, HS Valve & Expansion Valve. Terminal HEPA filters: to filter 0.3micron and larger particles at >999.97% efficiency installed in specially designed insulated Plenum GI powder coated, installed in false ceiling in such a way that the first air coming into the room is better than Class 100. with all provisions for HEPA filter Integrity test at Site. 9 Perfilters: for particles in the range of 10 microns & 5 microns - non woven fabric, cleanable media with aluminum support mesh; to match AHU capacity 6 Dacting Factory fabricated rectangular duct, GI, 24G 1 Insulation: durit insulated with cross-finked polycehylen of 1 msm thick. All ducts should be sealed and pressure itseld for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Damper vintuitible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Kisser smelhelic Gauge with fixture (1No) & Temperature & RH Display (1No). 10 Room pressure Magnehic Gauge with fixture (1No) & Temperature, RHD bisplay (1No). 11 AhU & Condensing Units including control Panel to the AHU & Condensing Units including control Viring. Themoresstr, 3 KW Heaters, Humidistat Wiring.		capacity 10TR, pre-filters, bypass damper, fresh air arrangement	
Refrigerant piping: Hard-drawn Copper pipes with accessories, fittings, supports, tubular nitrile foam insulation complete with leak free brazed joints (up to 8 meters per circuit), N ₂ pressure tested, vacuum held & R407/R410a refrigerant charged, including Drior, HS Valve & Expansion Valve. Preminal HEPA filters: to filter 0.3micron and larger particles at >99.97% officiency installed in specially designed insulated Plenum GI powder coated, installed in false ceiling in such a way that the first air coming into the room is better than Class 100, with all provisions for HEPA After Integrity test at Site. Prefilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity Image in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity Image information: ducts finalued with cross-linked polyethylene of 13mm thick. All ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. Volume control (GT-1RG) duct Dampers – manual with handl with gradation markings and lock. Fire Damper withfusible link and limit witch to cult off power to AHU in case of fire. Return Air Risers embedded within wall panels with extraded aluminum Grills for tool weel pickup. It should have modular. EPS (TT grade) insulated Construction of class 1000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PCI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc. finkshings to cover the exposed EPS material difference enery to the CR, there should Clean		etc. to achieve Class 1000/10000 cleanliness. It should have a	
Refrigerant piping: Hard-drawn Copper pipes with accessories, fittings, supports, tubular nitrile foam insulation complete with leak free brazed joints (up to 8 meters per circuit), N ₂ pressure tested, vacuum held & R407/R410a refrigerant charged, including Drior, HS Valve & Expansion Valve. Preminal HEPA filters: to filter 0.3micron and larger particles at >99.97% officiency installed in specially designed insulated Plenum GI powder coated, installed in false ceiling in such a way that the first air coming into the room is better than Class 100, with all provisions for HEPA After Integrity test at Site. Prefilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity Image in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity Image information: ducts finalued with cross-linked polyethylene of 13mm thick. All ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. Volume control (GT-1RG) duct Dampers – manual with handl with gradation markings and lock. Fire Damper withfusible link and limit witch to cult off power to AHU in case of fire. Return Air Risers embedded within wall panels with extraded aluminum Grills for tool weel pickup. It should have modular. EPS (TT grade) insulated Construction of class 1000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PCI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc. finkshings to cover the exposed EPS material difference enery to the CR, there should Clean		motor blower of capacity 5300cfm or higher.	
3 fittings, supports, tubular nitrile foam insulation complete with leak free brazed joints (up to 8 meters per circuit), N ₂ pressure tested, vacuum held & R407c/R410a terrigeran charged, including Drier, HS Valve & Espansion Valve. 4 Population of the terrigeran charged, including Drier, HS Valve & Espansion Valve. 4 S99.97% efficiency installed in specially designed insulated 4 Penum GI powder coated, installed in false ceiling in such a way that the first air coming into the room is better than Class 100, with all provisions for HEPA filter Integrity test at Site. 5 Prefilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity. 6 Ducting Factory fabricated rectangular duct, GI, 24G 7 Insulation: ducts insulated with cross-linked polyethylene of 13 mit tick. All ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sulfight with 0.4 mit durins and here. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withriksible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers endedd within sque low timg. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the AHU & Condensing Units including cottorul wiring. 11 AHU			
leak free brazed joints (up to 8 meters per circuit), N ₂ pressure tested, vacuum held & R407cR410a refrigerant charged, including Drier, HS Valve & Expansion Valve. 4 -99.97% efficiency installed in specially designed insulated Plenum GI powder coated, installed in false celling in such a way that the first air coming into the room is better than Class 100, with all provisions for HEPA filter Integrity test at Site. 5 Prefilters: for particles in the range of 10 microns & 5 microns - non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity. 6 Ducting Factory fabricated rectangular duct; GI, 24G 7 Instalation: ducts insulated with cross-linked polyethylene of 13mm thick. All ducts should be scaled and pressure tested for leaks before beginning insulation work. Cladding or external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to catoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for tow level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). 11 AHU & Condensito 1000 level pickup. 12 class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, PUg sockets, View Panels, other utilities etc. flashings to cover the exposed EPS material for Diffusers. Lighting, Grilles, H	3		
tested, vacuum field & P.407:07410a refrigerant charged, including Drier, HS Valve & Expansion Valve. 4 299.97% efficiency installed in specially designed insulted 9 10 10 11 11 12 12 13 14 14 15 15 16 16 17 18 16 17 18 16 16 17 18 18 19	5		
Drier, HS Valve & Expansion Valve. 2 Terminal HEPA filters: to filter 0.3micron and larger particles at >>9.97% efficiency installed in specially designed insulated 4 Penum GI powder coated, installed in false ceiling in such a way that the first air coming into the room is better than Class 100, with all provisions for HEPA filter Integrity test at Site. Prefilters: for particles in the range of 10 microns & 5 microns - non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity 6 Ducting Factory fibricated retrangular duct, GI, 24G Insulation: ducts insulated with cross-linked polyethylene of 13mm thick. All ducts should be scaled and pressure tested for leaks before beginning insulation work. Cladding or external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to curof Power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for tow level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the 14 AHU & Condensing Units including control wiring, Thermostat. 3 KW Heaters, Humidistat wiring. 11 It should have modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Will panels (80mm thick) with bot sides 0.55mm thick PPG includuing cutous in the panels for Grilles, Plug sockets, Vie			
Terminal HEPA filters: to filter 0.3micron and larger particles at 499.97% efficiency installed in specially designed insulated Plenum GI powder coated, installed in false celling in such a way that the first air coming into the room is better than Class 100, with all provisions for HEPA filter Integrity test at Sine. 5 Prefilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity 6 Ducting Factory fabricated rectangular duct, GI, 24G 7 Insulation: ducts insulated with ross-linked polyethylene of 13mm thick. All ducts should be scaled and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. with gradation markings and lock. Fire Damper withfusible link and limit switch to cluoff power to AHU in case of fire. 8 Volume control (GI : 18G) duct Dumpers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to cluoff power to AHU in case of fire. 9 Return Air Riscr schedded within will pancles with extruded aluminum Grills for low level pickup.			
4 >>999.97% efficiency installed in specially designed insulated 9 Penum GI powder coated, installed in false ceiling in such a way that the first air coming into the room is better than Class 100, with all provisions for HEPA filter Integrity test at Site. 5 Prefilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity 6 Ducting Factory fabricated rectangular duct, G1, 24G 1 Insulation: ducts insulated with cross-linked polyethylene of 13mm thick. All ducts should be easeled and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to soulight with 0.4mm aluminum sheet. 8 Volume control (G1 - 18G) duct Dumpers - manual with handle with gradation markings and lock. Fire Damper withrüshible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fisture (1No) & Temmostat, 3 KW Heaters, Humidistat wiring. 11 AHU & Condensing Units including control wiring. 12 class 1000 Clean room Wall Panels (80mm thick with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc. ficalsings to cover the exposed EPS material and provision for concealed wiring. Return Air Risers. 13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides 0.55mm thi		Drier, HS Valve & Expansion Valve.	
4 Plenum GI powder coated, installed in false ceiling in such a way that the first air coming into the room is better than Class 100, with all provisions for HEPA filter Integrity test at Site. 5 Profilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity 6 Ducting Factory fabricated rectangular duct, GI, 24G 7 Insulation: ducts insulated with ross-linked polyethylene of 13mm thick. All ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and lamit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). 11 Adult & Condensing Units including control Wing, Thermostat, 3 KW Heaters, Humidistat wiring. 11 at should have modular, EPS (TF grade) insulated Construction of consels of Grilles, Plug socket S, View Panels, Other utilities etc. flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers each 1000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 95.5mm thick including cutouts in the panels for Grilles, Plug obisulated Construction of class 10,000 and class 1000 Clean toom Filing of the set of the design 1000 filting, Gri		Terminal HEPA filters: to filter 0.3micron and larger particles at	
4 Plenum GI powder coated, installed in false ceiling in such a way that the first air coming into the room is better than Class 100, with all provisions for HEPA filter Integrity test at Site. 5 Profilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity 6 Ducting Factory fabricated rectangular duct, GI, 24G 7 Insulation: ducts insulated with ross-linked polyethylene of 13mm thick. All ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and lamit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). 11 Adult & Condensing Units including control Wing, Thermostat, 3 KW Heaters, Humidistat wiring. 11 at should have modular, EPS (TF grade) insulated Construction of consels of Grilles, Plug socket S, View Panels, Other utilities etc. flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers each 1000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 95.5mm thick including cutouts in the panels for Grilles, Plug obisulated Construction of class 10,000 and class 1000 Clean toom Filing of the set of the design 1000 filting, Gri	4	>99.97% efficiency installed in specially designed insulated	
that the first air coming into the room is better than Class 100, with all provisions for HEPA filter Integrity test at Site. 5 76 10 6 Ducting Eactory fabricated rectangular duct, G1, 24G 7 1 2 2 3 3 4 1 4 1 4 1 4 4 1 <td>4</td> <td></td> <td></td>	4		
with all provisions for HEPA filter Integrity test at Site. 5 Profilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity 6 Ducting Factory fabricated rectangular duct, GI, 24G 7 Insulation: ducts insulated with cross-linked polyethylene of leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limits witch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). 8 Scope includes the electrical Work from Control Panel to the 11 AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. 12 class 10.000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc. flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. 13 Modular, EPS (TF grade) insulated Construction of class 10.000 and class 1000 Clean room Cilling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grill			
5 Prefilters: for particles in the range of 10 microns & 5 microns – non-woven fabric, cleanable media with aluminum support mesh: to match AHU capacity 6 Ducting Factory fabricated rectangular duct, GI, 24G 7 Insulation: duct is mosal-tack dup locylethylene of 13mm thick. All ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1No). Scope includes the electrical Work from Control Panel to the AHU & Condensing Units including control wring, Thermostat, 3 KW Heaters, Humidistat wring. 11 AHU & Condensing Units including cutouts in thick) with both sides 0.55mm thick PPG (Te grade) insulated Construction of conceald wring, Return Air Risers. 12 It should have modular, EPS (TF grade) insulated Construction of concealed wring, Return Air Risers. 13 Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 10.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material for Diffusers, Lighting, Grilles		-	
3 non-woven fabric, cleanable media with aluminum support mesh; to match AHU capacity 6 Ducting Factory fabricated rectangular duct, GI, 24G 7 Ismutation: ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to culofl power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. 11 It should have modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc. flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. 13 Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coring: Aluminum sections to			
ionatch AHU capacity 6 Ducting Factory fabricated rectangular duct, GI, 24G 7 Insulation: ducts insulated with cross-linked polyethylene of 7 Insulation: ducts insulated with cross-linked polyethylene of 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to cutoff power to AHU in case of fire. 8 Volume control (GI - 18G) duct Dampers - manual with thandle with gradation markings and lock. Fire Damper withfusible link 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the 11 11 AHU & Condensing Units including control wring. Thermostat, 3 KW Heaters, Humidistat wiring. 12 class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PGI including cutouts in 14 the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for 12 class 1000 Clean room Ceiling Panels (50mm thick) with both sides PFGI 0.55mm thick including cutouts in the panels 13	5		
6 Ducting Factory fabricated rectangular duct, GI, 24G 7 Insulation: ducts insulated with cross-linked polyethylene of 13mm thick. All ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sonlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). 11 AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. 11 AHU & Condensing Units including control wire ducts (30mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc., flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. 13 Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall-ceiling-floor. 15 Gorder Coving: Die cast aluminum coving for corners. 16			
Insulation: ducts insulated with cross-linked polyethylene of 13mm thick. All ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (G1 - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). 11 AHU & Condensing Units including control Panel to the 11 AHU & Condensing Units including control wiring. 11 Thermostat. J SKW Heaters. Humidistat wiring. 12 class 10,000 and class 1000 Clear noom Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc. fashings to cover the exposed EPS material and provision for concealed wiring. Return Air Risers. 13 and class 1000 Clear noom Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90 ^o joints between wall-ceiling-floor. 15 corner Coving: Die cast aluminum coving for corners. 16 <td>6</td> <td></td> <td></td>	6		
1 13mm thick. All ducts should be sealed and pressure tested for leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusble link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the 11 AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. 12 class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with bot sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material construction of class 10,000 and class 1000 Clean room Hinged Door: Metallic powder coated with double glazed, Sb Bull bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 14 Coving: Dic east aluminum coving for corners. 15 Corner Coving: Die cast aluminum			
leaks before beginning insulation work. Cladding of external ducts directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the 11 AHU & Condensing Units including control wiring. Thermostat, 3 KW Heaters, Humidistat wiring. 11 class 10.000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc., flashings to cover the exposed EPS material and provision for concaled wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPG 10.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including fla	7		
directly exposed to sunlight with 0.4mm aluminum sheet. 8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the 11 AHU & Condensing Units including control wring, Thermostat, 3 KW Heaters, Humidistat wring. 12 class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc., flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. 13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope			
8 Volume control (GI - 18G) duct Dampers - manual with handle with gradation markings and lock. Fire Damper withfusible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. 11 AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. 12 class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc. flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. 13 Modular, EPS (TF grade) insulated Construction of class 10.000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall-ceiling-floor of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X.2. Im 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X.2. Im <			
with gradation markings and lock. Fire Damper withfusible link and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). 11 AHU & Condensing Units including control Panel to the AHU & Condensing Units including control wring, Thermostat, 3 KW Heaters, Humidistat wring. 11 stopp of the stopp o	8		
and limit switch to cutoff power to AHU in case of fire. 9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the 11 AHU & Condensing Units including control wring, Thermostat, 3 KW Heaters, Humidistat wring. 12 class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wring, Return Air Risers. 13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 18 View Panels: Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room			
9 Return Air Risers embedded within wall panels with extruded aluminum Grills for low level pickup. 10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). 11 AHU & Condensing Units including control Viring, Thermostat, 3 KW Heaters, Humidistat wiring. 11 AHU & Condensing Units including control Viring, Thermostat, 3 KW Heaters, Humidistat wiring. 12 It should have modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. 13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wallceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double			
10 Room Pressure Magnehelic Gauge with fixture (1No) & Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the 11 AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. 12 It should have modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. 13 Modular, EPS (TF grade) insulated Construction of class 10,000 13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1 m 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fitxtures: Construction of class 10,000 and class 10,000 Clean room light fittings with LED lamps of suitable wa	9		
Temperature & RH Display (1 No). Scope includes the electrical Work from Control Panel to the 11 AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. It should have modular, EPS (TF grade) insulated Construction of 12 class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc. flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. 15 Construction of class 10,000 and class 1000 Clean room Hinged 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 18 View Panels: Double glazed, with flush mounting; Size: 900 X			
Scope includes the electrical Work from Control Panel to the 11 AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. 12 It should have modular, EPS (TF grade) insulated Construction of 12 class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m X 2.1m 18 View Panels: Double glazed, with flush mounting; Size: 900 X	10	Room Pressure Magnehelic Gauge with fixture (1No) &	
11 AHU & Condensing Units including control wiring, Thermostat, 3 KW Heaters, Humidistat wiring. 12 It should have modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. 13 Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
Thermostat, 3 KW Heaters, Humidistat wiring. It should have modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc., flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. Construction of class 10,000 and class 1000 Clean room Hinged 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radia		Scope includes the electrical Work from Control Panel to the	
It should have modular, EPS (TF grade) insulated Construction of 12 It should have modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 900 X 1000mm with 1 or 2 partitions including sun control film t	11	AHU & Condensing Units including control wiring,	
It should have modular, EPS (TF grade) insulated Construction of 12 It should have modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 900 X 1000mm with 1 or 2 partitions including sun control film t			
12 class 10,000 and class 1000 Clean room Wall Panels (80mm thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. 13 Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wallceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room Light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
thick) with both sides 0.55mm thick PPGI including cutouts in the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 900mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable	12		
the panels for Grilles, Plug sockets, View Panels, other utilities etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with			
etc, flashings to cover the exposed EPS material and provision for concealed wiring, Return Air Risers. Modular, EPS (TF grade) insulated Construction of class 10,000 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall-ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Construction of class 10,000 and class 1000 Clean room Hinged 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
concealed wiring, Return Air Risers.13131314151716171718181910101011111213141415151516161717171819191000mm with 1 or 2 partitions including sun control film to reduce radiation19191010111515151516171819191910019100100110121213141515151515161717181919100			
Modular, EPS (TF grade) insulated Construction of class 10,000 13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall-ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Construction of class 10,000 and class 1000 Clean room Hinged 16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
13 and class 1000 Clean room Ceiling Panels (50mm thick) with both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall-ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Construction of class 10,000 and class 1000 Clean room Hinged 17 Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
both sides PPGI 0.55mm thick including cutouts in the panels for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material 14 Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 10,000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material14Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor.15Corner Coving: Die cast aluminum coving for corners.16Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m17Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included.18View Panels: Double glazed, with flush mounting; Size: 2000 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation19Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage.20Epoxy flooring: Self leveling, seamless floor with suitable surface	13	and class 1000 Clean room Ceiling Panels (50mm thick) with	
for Diffusers, Lighting, Grilles, HEPA Plenum, other utilities etc. including flashings to cover the exposed EPS material14Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor.15Corner Coving: Die cast aluminum coving for corners.16Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m17Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included.18View Panels: Double glazed, with flush mounting; Size: 2000 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation19Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage.20Epoxy flooring: Self leveling, seamless floor with suitable surface		both sides PPGI 0.55mm thick including cutouts in the panels	
etc. including flashings to cover the exposed EPS material14Coving: Aluminum sections to round off 90° joints between wall- ceiling-floor.15Corner Coving: Die cast aluminum coving for corners.16Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m17Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included.18View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation19Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage.20Epoxy flooring: Self leveling, seamless floor with suitable surface			
14 Coving: Aluminum sections to round off 90° joints between wall-ceiling-floor. 15 Corner Coving: Die cast aluminum coving for corners. 16 Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
ceiling-floor.15Corner Coving: Die cast aluminum coving for corners.16Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m17Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included.18View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation19Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage.20Epoxy flooring: Self leveling, seamless floor with suitable surface	14		
15 Corner Coving: Die cast aluminum coving for corners. 16 Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface	1.		
16 Construction of class 10,000 and class 1000 Clean room Hinged Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface	15		
16 Doors: Metallic powder coated with double glazed, SS ball bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
bearing hinges, View panel, door closer, SS handle etc., Size: 1.2 X 2.1m 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface	16		
X 2.1m Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
17 Before entry to the CR, there should be a gowning area. Scope of the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
17 the designing of the gowning area is also included. 18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface	1-		
18 View Panels: Double glazed, with flush mounting; Size: 900 X 900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface	17		
900mm. Double glazed, with flush mounting; Size: 2000 X 1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface	18		
1000mm with 1 or 2 partitions including sun control film to reduce radiation 19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface			
19 Lighting fixtures: Construction of class 10,000 and class 1000 Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface		1000mm with 1 or 2 partitions including sun control film to	
Clean room light fittings with LED lamps of suitable wattage. 20 Epoxy flooring: Self leveling, seamless floor with suitable surface		reduce radiation	
20 Epoxy flooring: Self leveling, seamless floor with suitable surface	19		
preparation, 3mm total thickness.	20		
		preparation, 3mm total thickness.	

21	Sockets: 15/5A in the Wall Panels / Partitions.	
22	Scope includes all wiring for lighting, sockets & switches complete within the Construction of class 10,000 and class 1000	
	Clean room area, including cutouts & conduits in Wall Panels.	
23	Smoke Detection and Alarm System: Conventional sensors (8Nos), Conventional control panel, Manual Call Point, Response Indicator, Audio-visual alarm, wiring/cabling	
24	Biometric Door Access Control System: with software, EM lock, exit push button, Switched -mode power supply, cable, clamp & accessories	
25	Construction of class 10,000 and class 1000 Clean room compatible 2 number of SS Table Size 5' x 3' x 2.5' and 4 height adjustable stools to sit.	
26	With the financial bid, vendor should also submit the cost of AMC valid for 3 years including all consumables and labor charges.	
27	Vendor may visit the site before submitting their bids.	
	Site Location : HSB Room No 262, Department of Physics.	

(Note: It is mandatory for the bidders to provide the compliance statement in tabular column format along with catalogue page number (comply/not comply) for the above points with document proof as required. Failing which bidders will be technically disqualified)

SIGNATURE OF BIDDER ALONG WITH SEAL OF THE COMPANY WITH DATE

FINANCIAL BID (PROFORMA) - BILL OF QUANTITIES (BOQ)

Item Name: "Construction of class 10,000 and class 1000 Clean room " Tender No. PH/ABHI/06/IOE23/CLEANROOM

It. No	Description of work	Quantity	Units	Basic Rate in INR	GST in Percentage	Total Amount with taxes in INR
1	Construction of class 10,000 and class 1000 Clean room	1	Nos.			
2	AMC valid for 3 years including all consumables and labor	1	Nos.			
	Grand Total					

Total Amount Rupees in words _____



CENTRE FOR INDUSTRIAL CONSULTANCY & SPONSORED RESEARCH (IC&SR) INDIAN INSTITUTE OF TECHNOLOGY MADRAS CHENNAI 600 036



ELECTRONIC CLEARING SERVICE (Credit Clearing)/ REAL TIME GROSS SETTLEMENT (RTGS) FACILITY FOR RECEIVING PAYMENTS A. Details of Account Holder

Name of the Institution	Indian Institute of Technology - Madras
Complete Contact Address	Industrial Consultancy and Sponsored Research Indian Institute of Technology-Madras, IIT- Madras Campus Post Office, Sardar Patel Road, Guindy, CHENNAI - 600 036
Telephone No./ Fax No.	Tel - 044-2257 8356
E- mail ID of the FO/AO/REG/DIR	dricsr@iitm.ac.in

B. Bank Account Details:

Institution Account Name (As per Bank	The Registrar, Indian Institute of
Record)	Technology - Madras
Account No.	2722101003872
Account Print Name	IIT F A/C , The Registrar IIT Madras
IFSC CODE	CNRB0002722
Bank Name (in full)	Canara Bank
Branch Name	IIT-Madras Branch
Complete Branch Address	Canara Bank,
	IIT-Madras Branch,
5	IIT- Madras Campus Post Office,
	Sardar Patel Road,
	Guindy, CHENNAI - 600 036
MICR No.	600015085
Account Type	Savings Account

Certified that the Institute's account is in an RTGS enabled branch.

I hereby declare that the particulars given above are correct and complete.

Date:

Signature of the competent Authority of the Institution with seal.

FORMAT FOR AFFIDAVIT OF SELF-CERTIFICATION UNDER PREFERENCE TO MAKE IN INDIA – PER ITEM

Tender Reference Number:

Name of the item / Service:

Date: _____ I/We_____S/o, D/o, W/o, _____ Resident of

Hereby solemnly affirm and declare as under:

That I will agree to abide by the terms and conditions of the Public Procurement (Preference to Make in India) Policy vide GoI Order no. P-45021/2/2017-PP (B.E.-II) dated 15.06.2017 (subsequently revised vide orders dated 28.05.2018, 29.05.2019and 04.06.2020) MOCI order No. 45021/2/2017-PP (BE II) Dt.16th September 2020 & P- 45021/102/2019-BE-II-Part (1) (E-50310) Dt.4th March 2021 and any subsequent modifications/Amendments, if any and

That the local content for all inputs which constitute the said item/service/work has been verified by me and I am responsible for the correctness of the claims made therein.

Tick (🗸	() and Fill the Appropriate Category
	I/We[name of the supplier] hereby confirm in respect of quoted items
	thatLocal Content is equal to or more than 50% and come under "Class-I Local Supplier"
	category.
	I/We[name of the supplier] hereby confirm in respect of quoted items
	that Local Content is equal to 20% but less than 50% and come under "Class-II Local Supplier"
	category.
• Th	he details of the location (s) at which the local value addition is made and the proportionate value of loca
cor	ntent in percentage
Addrog	Barcontago of Local content: 0/

Address _____ ___

Percentage of Local content: _____%

Authorized signatory (To be duly authorized by the Board of Directors) <Insert Name, Designation and Contact No.>

[Note: In case of procurement for a value in excess of Rs. 10 Crores, the bidders shall provide this certificate from statutory auditor or cost auditor of the company (in the case of companies) or from a practicing cost accountant or practicing chartered accountant (in respect of suppliers other than companies) giving the percentage of local content.]

This letter should be on the letterhead of the quoting firm and should be signed by a competent authority. Nonsubmission of this will lead to Disqualification of bids.

<u> Annexure – F</u>

(To be given on the letter head of the bidder)

No._____

Dated: _____

CERTIFICATE

(Bidders from India)

I have read the clause regarding restrictions on procurement from a bidder of a country which shares a land border with India and hereby certify that I am not from such a country.

OR (whichever is applicable)

(Bidders from Country which shares a land border with India)

I have read the clause regarding restrictions on procurement from a bidder of a country which shares a land border with India and hereby certify that I from ______ (Name of Country) and has been registered with the Competent Authority. I also certify that I fulfil all the requirements in this regard and is eligible to be considered. (Copy/ evidence of valid registration by the Competent Authority is to be attached)

Place: Date: Signature of the Tenderer Name & Address of the Tenderer with Office Stamp